


SRUJHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division

Schedule-B

NAME OF THE WORK: Improvements to CC roads 10th,11th,12th cross roads at Ravindra Nagara in ward no. 13 in Shettyhalli sub division

Sl. No	Description of work	Unit	Qty	Rate to be Quoted by Contractor K.Jagadish	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specifications and directions of engineer in charge of the work	Cum	469.26	182.07	Rupees One Hundred Eighty Two and Seven Paise Only
2	Construction Of granular sub -base by providing coarse graded crushed stone aggregates of granite / trap / basalt material spreading in uniform layers with motor grader on prepared surface,mixing by mix in place method with rotavator at OMC,and compacting with vibratory roller to achieve the desired density. complete as per specification. By mix in place method for Grading II Material KSSRB complete as per specifications and directions of engineer in charge of the work	Cum	156.42	1637.5	Rupees One Thousand Six Hundred Thirty Seven and Fifty Paise Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 complete as per specifications and directions of engineer in charge of the work	Cum	156.42	5338.04	Rupees Five Thousand Three Hundred Thirty Eight and Four Paise Only





Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

4	Cement concrete pavement. Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregates, with superplasticiser @3lts confirming to IS9103-1999 Reaffirmed-2008, mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing) & spreading the concrete with shovels, rammers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane, sealant primer, joint sealant, admixtures as approved, including curing, finishing to lines and grades as per drawing complete as per specifications.M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum) complete as per specifications and directions of engineer in charge of the work	cum	424.28	6433.72	Rupees Six Thousand Four Hundred Thirty Three and Seventy Two Paise Only
5	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillers, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement complete as per the direction of Engineer-in-charge of the work.	Rmtr	271.50	126.13	Rupees One Hundred Twenty Six and Thirteen Paise Only


Signature of the Contractor


Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP